

ADDENDUM THREE

Addendum Three to the drawings and specifications prepared by Myszak + Palmer for **Linton Sports Support Facility** for **Linton Stockton School Corporation**, Linton, Indiana.

All Contractors bidding on this project shall read all of the items covered below and shall comply with all of the requirements as set forth, including any necessary refinements or additions generated by this Addendum and required by the intent of the original contract documents. All Contractors shall acknowledge on their bid form that they have received this Addendum, Subsequent Addenda, and include the appropriate content of same within their bid proposal

ADDENDUM THREE

DRAWING CLARIFICATION

1. ST1.2, A1.1, A3.1 and A4.1 CMU / FOUNDATION - REVISION

- A. All exterior walls shall have 8" medium weight CMU in lieu of 6" CMU. The wall makeup at the entire exterior of the building would now be 8" CMU, 1-3/4" Insulation, 1" air space, and 4" split faced block.
- B. The foundation walls at the exterior wall shall be 14" thick.

Pages 1 through 1 constitute the total makeup of **Addendum Three** with attached drawings and other supporting data following page 0. Contractor shall notify Architect if all pages are not received.

