

ADDENDUM THREE

Addendum Three to the drawings and specifications prepared by Myszak + Palmer for **Pantheon Business Theatre Renovations** for **Pantheon Board of Directors**, Vincennes, Indiana.

All Contractors bidding on this project shall read all of the items covered below and shall comply with all of the requirements as set forth, including any necessary refinements or additions generated by this Addendum and required by the intent of the original contract documents. All Contractors shall acknowledge on their bid form that they have received this Addendum, Subsequent Addenda, and include the appropriate content of same within their bid proposal

ADDENDUM THREE

SPECIFICATIONS

1. Section 230901, 230993

- A. AHU control: wall mount thermostats with integral heating/cooling staging and twinning of compressors, blower fans, and burners. Stats to provide 7-day programmable with setback and be compatible with variable speed fans and compressors. Alarm notification for low space temperature not required.
- B. EF control: Exhaust fans are on occupancy sensors.
- C. CH control: Cabinet heaters to be provided with integral thermostats.
- D. FC Control: Fan coils to be powered thru heat pump unit and controlled by compatible wall mount, programmable thermostats.

2. Drawing M.4

DRAWING CLARIFICATION

- A. Change supply air duct from AHU-7 and AHU-8 to round spiral, galvanized steel duct with round to rectangular boots. Size duct for .05" static pressure loss.

Pages 1 through 1 constitute the total makeup of **Addendum Three** with attached drawings and other supporting data following page 1. Contractor shall notify Architect if all pages are not received.

myszak + palmer
ARCHITECTS

